



## **NOTICE INVITING TENDER**

The Police Department Government of Sindh invites sealed tenders from eligible Bidders / Firms registered with Pakistan Engineering Council, Income Tax Department & Revenue Board for the repair of Rapid Response Force (RRF) Sindh, Karachi for the current financial year 2017-18.

S #	Name of Work	Bid Security	Estimated Cost in Rs. (Millions)	Tender Fee Rs.	Time for Completion
1	Repair / Renovation work for RRF Alfalah Base Karachi	5 %	20	2,000	2 Month

2/- Complete Details are available in Tender documents, which can be purchased from the office of the DIGP / Commandant RRF Sindh Karachi near Korangi Creek Karachi from 23-04-18 till 09-05-18 during office hours by submitting an application on their letter head along with tender fees (nonrefundable) and can also be downloaded from the Sindh Police website ([www.sindhpolice.gov.pk](http://www.sindhpolice.gov.pk)) or SPPRA website ([www.spprasindh.gov.pk](http://www.spprasindh.gov.pk)).

3/- Single Stage One Envelop procedure will be followed, Bids in sealed envelopes should be submitted / dropped in the tender box kept in office of the DIGP / RRF Sindh Karachi near Korangi Creek Karachi up-to 10-05-18 till 1500 hrs. The Bid shall be opened on the same day 10-05-18 at 1530 hrs and at the same venue in the presence of Bidding Committee and intending bidders who choose to be present on the occasion.

4/- Un-responded tender will be again issued from 11-05-18 to 25-05-18 during office hours and sealed bids should be submitted / dropped in the tender box kept in office of the DIGP / RRF Sindh Karachi near Korangi Creek Karachi up-to 26-05-18 till 1500 hrs and shall be opened at 26-05-18 at 1530 hrs at the same venue.

5/- Bid Security 5% of the total bid in the form of Pay Order in favor of the DIGP / Commandant Rapid Response Force Sindh Karachi should be submitted with Bids.

6/- Only bids offered on the prescribed tender form issued by the police department shall be accepted. However, additional sheets may be attached, if required.

7/- Conditional tender / application will not be entertained.

8/- In case of public holiday the bids should be submitted and opened on the next working day.

9/- The Procuring Agency may reject any or all bids or postpone date as per relevant provisions of SPP Rules, 2010.

Sd/-  
ADIGP  
For DIGP/ Commandant RRF,  
Sindh, **Karachi**.

**NAME OF WORK:- REPAIR /RENOVATION WORK FOR AT R.R.F AL-FALAH BASE KARACHI**

**SCHEDULE "B"**

**PART-A- FOUNDATION**

S.NO:	DESCRIPTION OF TEMS	QUANTITY	RATE	UNIT	AMOUNT
01	Excavation in foundation of bldgs bridges and other structure i/c dag belling dressing refilling around structure with excavated earth watering and ramming lead upto one chain and lift upto 5' in hard soil or soft murum. (S.I.NO: 18-c P/04 )	23231.00Sft::	3554/38	%0Cft:	82572/-
02	Cement concrete brick or stone ballast 1-1/2" to 2" to guage ratio: 1:4:8. (S.I.NO: 4 -c P/15 )	9197.00Cft:	9416/28	%Cft:	866015/-
03	Fabrication of rinf: for C.C. i/c cutting bending laying in position making joints and fastening i/c cost of binding wire also i/cs removal of rust from bars. (S.I.NO: 5 -f P/16 )	239.64 Cwt:	5001/70	P.Cwt:	1198607/-
04-a	R.C.C. Work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately this rate also i/c all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface i/c screening and finishing the exposed surface i/c screening and washing of shingle R.C. work in roof slab, beams cols, rafts, lintels and other structural members laid in position complete in all respect ratio 1:2:4 (90 lbs) cement 2 cft. Sand 4 cft. Shingle 1/8" to 1/4" gauge. (S.I. No.6-a/19)	4987.00Cft:	337/-	P.Cft:	1680619/-
4-b	Ratio: R.C.C. 1:1:1/2:3	331.00Cft:	349/-	P.Cft:	115519/-
05	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing at stone aggregate without shuttering ( Ratio: 1:3:6 ) (S.I.NO: 05 P/16 )	1835.00Cft:	12595/50	%Cft:	231118/-
06	Errection and removal of centering for R.C.C. or plain cement concrete works of deodar wood (2 <sup>nd</sup> class) for Partal Wood (ii) verticalk (S.I.NO: 19 -b -ii P/18 )	5397.00Sft	3127/41	%Sft:	168786/-
07	Filling watering and ramming earth in floor with surplus earth from foundation lead upto one chain and lift upto 5'. (S.I. No.21/5)	5214.00Cft:	1512/50	%0Cft:	7886/-
08	Filling Watering & Ramming Earth under Floor with new earth (Excavated from outside) lead upto one chain and lift upto 5 feet. (S.I.No.22/P-4)	15876.00Cft:	3630/-/-	%Cft:	38730/-
09	Cement Plaster (1:4) upto 20" height 3/4" thick. (S.I. No.13/58)	1215.00Sft:	3191/76	%Sft:	36641/-

10	Providing and laying 1" thick topping cement concrete (1:2:4) i/c surface finishing and dividing 3" thick.	18700.00Sft:	4411/83	P.Sft:	825012/-
		TOTAL RS:-			5251505/-

#### **PART-B- GROUND FLOOR**

S.NO:	DESCRIPTION OF TEMS	QUANTITY	RATE	UNIT	AMOUNT
01-a	R.C.C. Work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately this rate also i/c all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface i/c screening and finishing the exposed surface i/c screening and washing of shingle R.C. work in roof slab, beams cols, rafts, lintels and other structural members laid in position complete in all respect ratio 1:2:4 (90 lbs) cement 2 cft. Sand 4 cft. Shingle 1/8" to 1/4" gauge. (S.I. No.6-a/19)	11838.00Cft:	337/-	P.Cft:	3989406/--
1-B	R.C.C. 1:1:1/2:3	2040.00 Cft:	349/-	P.Cft:	711960/-
02	Fabrication of rinf: for C.C. i/c cutting bending laying in position making joints and fastening i/c cost of binding wire also i/cs removal of rust from bars. (S.I.NO: 5 -f P/16 )	634.17 Cwt:	5001/70	P.Cwt:	3171928/-
03	Providing and laying 1:3:6 Cement concrete solid block masonry wall above 6" in thickness set in 1:6 cement mortar in G/floor super structure i/c raking out joints & curing etc. (S.I.NO: 23 -f P/19 )	4461.0Cft:	14621/44	%Cft:	652262/-
04	Providing and laying 1:3:6 cement concrete solid block masonry wall 6" and below in thickness set in 1:6 cement mortar in G/floor super structure i/c racking out joints & curing etc: (S.I.NO: 24 P/19 )	535.00Cft:	15771/01	%Cft:	84375/-
05	Cement Plaster (1:4) upto 12' height (c) 3/4" thick. (S.I. No.11-c P/52)	26730..00Sft:	3015/76	%Sft:	806112/-
06	Extra for lime mud or cement plaster and pointing from 12'and above ( for each additional 10' height). (S.I. No.29-c P/54)	21870.00Sft:	140/97	%Sft:	30830/-
07	Providing and laying 1" thick topping cement concrete (1:2:4) i/c surface finishing and dividing 2"thick.	19044.00Sft:	3275/50	%Sft:	623786/-
08	Distempering in Three Coats . (S.I.No.24-c/P-54)	20934.00Sft	1079/65	%Sft:	226014/-
09	Preparing new surface and painting with matt: finish i/c rubbing the surface with Bathy silicon carbide rubbing brick) filling the voids with zink /chalk /plaster of paris mixture applying first coat premix making the surface smooth and then painting 3	24444.00Sft:	3444/38	%Sft:	841944/-

	coats with matt finish of approved make etc complete ( New surface in three coats). (S.I.No.36-a P/55)				
11	Making and fixing grating in opening i/c fixing at site with flat iron 2"x 3/8" and 3/4" sq: bars at 4" centre to centre. (S.I.NO: 25 P/92)	432.00Sft:	293/15	%Sft:	126641/-
12	P/F colour crete to wall surface to provide durable crust and aestheties having thickness upto 3/4"with specified colour having water fire and temnite resaistance ( upto 20-0 height). (S.I.No.44 /P-56)	5400.00Sft:	6319/50	%Sft:	341253/-
	TOTAL RS:-				11606511/-

# ANNUAL PROCUREMENT PLAN (WORKS, GOODS & SERVICES)

Financial Year 2017-18

Rapid Response Force (RRF) Sindh, Karachi

Repair of Building

S #	Description (Where Applicable)	Quantity (Where Applicable)	Estimated Unit Cost (Where Applicable)	Estimated Total Cost	Funds Allocated	Source of Funds (ADP/Non ADP)	Proposed Procurement Method	Timing of Procurement				Remarks
								1 <sup>st</sup> Qtr	2 <sup>nd</sup> Qtr	3 <sup>rd</sup> Qtr	4 <sup>th</sup> Qtr	
1	Office Building Repair			20 Million	Sindh Police	Non ADP	Single Stage One Envelope			3 <sup>rd</sup>	4 <sup>th</sup>	

Sd/-  
**(IMRAN RIAZ) PSP**  
ADIGP,  
For Commandant,  
Rapid Response Force (RRF),  
Sindh, Karachi.